

Standard toolbar with icons for Save, Print, Undo, Redo, and other functions. The status bar shows 'Security...' and '100%' zoom level.

A1 =

	A	B	C	D	E	F	G	H	I	J
1						Material	Labor	Labor	Other	TOTAL
2	Division	Costcode	Description	Quantity	Unit	\$	Hrs	\$	\$	\$
3	Sitework	020501610	Partition removal, brick	12.00	Sf	0.00	0.420	13.56	12.00	25.56
4	Sitework	020501630	Door removal, wood	4.00	Ea	0.00	3.840	123.84	1.24	125.08
5	Concrete	031001170	Forms, slab on grade, 1 use	120.00	Sf	178.80	9.000	490.80	0.00	669.60
6	Concrete	032001230	Reinf in place, columns, walls #4	320.00	Lb	124.80	4.480	243.20	0.00	368.00
7	Concrete	032001240	Reinf in place, columns, walls #6	360.00	Lb	136.80	4.320	234.00	0.00	370.80
8	Concrete	033001120	Concrete, 3000 psi, slabs &	1.00	Cy	105.31	0.320	14.44	8.13	127.88
9	Concrete	033001220	Concrete, 3000 psi, columns, by	1.00	Cy	105.31	1.050	47.39	15.31	168.01
10	DoorsWindow	082002130	Wood door, interior, hollow, 2'-6"x6'-	1.00	Ea	88.75	1.350	73.66	0.00	162.41
11	DoorsWindow	085001210	Aluminum window, fixed	1.00	Sf	21.25	0.150	8.19	0.00	29.44
12	DoorsWindow	086001265	Wood window, double hung, insul,	1.00	Ea	718.75	1.750	95.49	0.00	814.24
13	DoorsWindow	086001320	Wood window, awning, insul,	1.00	Ea	375.00	1.500	81.85	0.00	456.85
14	Finishes	092501410	Drywall, 5/8", ceiling, incl tape &	1.00	Sf	0.44	0.013	0.71	0.00	1.15
15	Finishes	093101220	Floor tile, ceramic, 6" x 6", average	1.00	Sf	4.38	0.062	3.39	0.00	7.77
16	Mechanical	152502130	Pipe insulation, fiberglass, 12" dia,	1.00	Lf	24.94	0.180	9.83	0.00	34.77
17	Mechanical	153001210	Sprinkler system, installed	1.00	Sf	0.00	0.000	0.00	2.94	2.94
18	Mechanical	153001220	Sprinkler head	1.00	Ea	8.88	0.400	21.83	0.00	30.71
19	Mechanical	154006110	Floor drain, plastic, 3"x3"	1.00	Ea	35.63	0.900	49.11	0.00	84.74
20	Mechanical	154007110	Water closet, with tank, floor	1.00	Ea	550.00	4.000	218.25	0.00	768.25
21										
22										
23										
24										
25										
26										